

# HIRE UNITS

# HUBER Sludge Acceptance Plant ROTAMAT® Ro3

## PACKAGED SLUDGE SCREENING

Tank mounted sludge screens complete with control panel, level controls and flow control valve. Suitable for screening of primary sludge, imported sludge and septic tank waste. Can also be used during over-pumping for screening raw sewage.

Robust stainless steel construction and fully frost protected.

#### **SPECIFICATION**

Flow capacity (sludge@3% d.s.)

Bar spacing

**Screenings capacity** 

Inlet connection

**Outlet connection** 

Washwater connection/required supply

**Electrical supply** 

Dry weight

#### Ro3/1200/6

80 l/s

6mm

2m3/hr

DN150/PN16 flange

DN300/PN16 flange

11/4 BSP/2.6 l/s@4-7 bar

20Amp x 400V-50HZ (3ph+N+E)

1800kg

### HIRE COSTS - PLEASE CONTACT US FOR HIRE COSTS

